SUMMARY OF QUANTITIES

Item No.	Spec. No.	Item Description	Unit	Estimated Quantity	Final Quantity
		BID PACKAGE NO. 1 - BASE BID			
1	01000	Mobilization - Bid Package No. 1	L.S.	1	
2	2A	Grubbing	Acre	11	
3	10A	18-Inch Class III RCP Storm Drainage Pipe	L.F.	140	
4	10B	24-Inch Class III RCP Storm Drainage Pipe	L.F.	115	
5	13A	SCDOT Type 112 Catch Basin	Each	2	
6	18A	Unclassified Excavation	C.Y.	19,500	
7	18B	Waste Excavation - Offsite Stockpile	C.Y.	14,500	
8	22A	6-Inch Thick Macadam Base Course (with prime)	S.Y.	1,100	
9	29A	Riprap for Pipe End Treatment and Pond Spillway	S.Y.	175	
10	29B	Grouted Riprap	S.Y.	300	
11	29C	Riprap for Erosion Control	Ton	150	
12	30A	Seeding (mulched)	Acre	21	
13	S-140A	Remove Existing Silt Fence	L.F.	705	
14	S-140B	Remove Existing Gate	Each	1	
15	S-190	Remove Pavement Markings	S.F.	20,000	
16	P-620	Permanent Reflective Pavement Markings	S.F.	58,000	
17	D-700A	Permanent Concrete Pond Riser Structure	L.S.	1	
18	D-700B	Sediment Trash Rack	Each	1	
19	E-891	Temporary Inlet Protection	Each	2	
20	E-893	Temporary Silt Fence	L.F.	1,300	
21	E-895A	Class A Temporary Erosion Control Matting	S.Y.	11,000	
22	E-895B	Class B Temporary Erosion Control Matting	S.Y.	2,100	
23	E-895C	Type 1 Permanent Turf Reinforcement Matting	S.Y.	200	
24	E-896	Temporary Sediment Tubes	L.F.	300	
25	T-905	Onsite Topsoil	C.Y.	10,200	
		BID PACKAGE NO. 1 - ADDITIVE BID NO. 1			
A1	S-190	Remove Pavement Markings	S.F.	5,000	
A2	P-620	Permanent Reflective Pavement Markings	S.F.	25,000	
		BID PACKAGE NO. 2			
1	01000	Mobilization - Bid Package No. 2	L.S.	1	
2	L-130	Glide Slope Shelter, Glide Slope Tower, Equipment,	L.S.	1	
		Electrical Service, Grounding System, Lightning Protection			
		System and Control Cable, Installed Complete			

AIKEN MUNICIPAL AIRPORT
AIKEN, SOUTH CAROLINA

THE LPA GROUP
TRANSPORTATION CONSULTANTS
A Unit of Michael Baker Corporation
Columbia, South Carolina
and other Major U.S. Cities

THE LPA GROUP INCORPORATED No. C00448 — CERTIFICATE OF AUTHORIZATION — SOUTH CAROLINA

LICENSED PROFESSIONAL ENGINEER No. 21252 — ANDY D. BUSBEE — SOUTH CAROLINA — 7-28-11

Designer:	Checked by:
DWC/CKM	ADB
Technician:	Project Number:
NWM	121913

REVISIONS

No.	Description	Date	By

Project Name:
RUNWAY 7
GLIDE SLOPE PROJECT
BID PACKAGE NO. 1

Drawing Name:
SUMMARY OF QUANTITIES

FAA A.I.P. Project Number:

Date:	Division:
AUGUST, 2011	AIRPORTS
Scale:	Sheet Number:
NONE	Drawing Number: Q-1

Q:\CLIENTS\Aiken\2010- RW 7 Glide Slope\DWG\MK-RW-GS-Q1.dwg Modified: Jul 28, 2011 - 11:51am Plotted: Jul 28, 2011 - 2:46pm MParrish